

ESTIMATE



**745 Atlanta Rd.
Suite 205
Cumming, GA 30040**

SAMPLE_BACK_YARD_DESIGN_PROPOSAL

Rep	Date	Estimate #
	1/1/2010	3295

Item	Description of Service	Qty:	Amount	Total
Softscapes	PRELIMINARY DESIGN		0.00	0.00
Hardscape Sales	<p>1. Provide a 2-D, Hand drawing and rendering of completed project</p> <p>PROJECT #1 - FRONT YARD RETAINING WALL</p> <p>1. At front right corner of house, remove existing cross tie retaining wall and dispose in 30 yard, on-site dump container</p> <p>2. Prepare new footing and install new retaining wall to approximately match length, height and contour of the existing wall.</p> <p>3. New wall shall be constructed using 6"x6" pressure treated timbers.</p> <p>4. Pricing shall include all #57 stone drainage backfill and 4" drain piping</p> <p>5. Remove existing juniper and holly shrubs along upper portion of retaining wall</p> <p>6. Upon completion of wall, the area above the wall, adjacent to the driveway, will be suitable for installing new plant material.</p> <p>7. Wall is approximately 40' long and we intend to finish the left side (closest to the street) by adding a small, 8' long, wing wall.</p> <p>8. Average wall height is approximately 4'-0"</p>			0.00

Total

By Signing Below, I agree to the pricing and scope of work listed above. I further agree to allow Sarros Landscaping, Inc. to provide these services on my property.

Signature: _____

Phone #	Fax #	E-mail	Web Site
(678) 201-5409	(770) 886-1682	phil@SarrosLandscaping.com	www.SarrosLandscaping.com

ESTIMATE



**745 Atlanta Rd.
Suite 205
Cumming, GA 30040**

SAMPLE_BACK_YARD_DESIGN_PROPOSAL

Rep	Date	Estimate #
	1/1/2010	3295

Item	Description of Service	Qty:	Amount	Total
Hardscape Sales	<p>PROJECT #2 - BACK YARD RETAINING WALL</p> <p>1. Remove all existing cross tie stairs and retaining wall and dispose in 30 yard, on-site dump container 2. Install new retaining wall and stairs in approximately the same location as the existing wall but adding another set of stairs and wall to accommodate a new patio area below the deck 3. Total area of this wall is approximately 345 square feet 4. Prepare new footing and install new retaining wall to approximately match length, height and contour of the existing wall. 5. New wall shall be constructed using 6"x6" pressure treated timbers. 6. Pricing shall include all #57 stone drainage backfill and 4" drain piping 7. Remove existing holly shrubs along upper portion of retaining wall 8. Prune existing Crepe Myrtle tree in this area 9. Upon completion of wall, the area above the wall, adjacent to the deck, will be suitable for installing new plant material.</p>			0.00
Hardscape Sales	<p>PROJECT #3 - FLAGSTONE PATIO</p> <p>1. Remove existing concrete slab at basement entry doors 2. Form and pour new, level concrete base pad 3. Install new Tennessee Flagstone patio below deck - approximately 21' x 11'</p>			0.00
Softscapes	<p>PROJECT #4 - BACK YARD SOD</p> <p>1. Re-grade back yard to create a smooth contour, eliminating the current peaks and valleys in the landscape 2. Remove all existing turfgrass and install 160 lbs, organic starter fertilizer 3. Install approximately 3500 square feet Fescue Sod (suitable to cover almost entire back yard) and roll seams upon completion</p>			0.00

Total

By Signing Below, I agree to the pricing and scope of work listed above. I further agree to allow Sarros Landscaping, Inc. to provide these services on my property.

Signature: _____

Phone #	Fax #	E-mail	Web Site
(678) 201-5409	(770) 886-1682	phil@SarrosLandscaping.com	www.SarrosLandscaping.com

ESTIMATE



**745 Atlanta Rd.
Suite 205
Cumming, GA 30040**

SAMPLE_BACK_YARD_DESIGN_PROPOSAL

Rep	Date	Estimate #
	1/1/2010	3295

Item	Description of Service	Qty:	Amount	Total
Softscapes	<p>PROJECT #5 - RIGHT SIDE YARD</p> <p>1. Upon completion of all other work, regrade the right side of the house where construction equipment has accessed the back yard. 2. Install (2) pallets Bermuda Sod where existing sod has been damaged. 3. Re-create new, curved bed-line along this side of the house 4. In new bed area, install (5), #3 gallon Waxleaf Ligustrum shrubs and (5), #3 gallon Pink Gumpo Azalea</p>			0.00
Softscapes	<p>PROJECT #6 - MULCH</p> <p>1. Upon completion of all projects, install (15) cubic yards Pine Bark Mini-Nugget Mulch in all bed areas in the back yard and right side yard including the area above the retaining wall adjacent to the driveway.</p>			0.00

By Signing Below, I agree to the pricing and scope of work listed above. I further agree to allow Sarros Landscaping, Inc. to provide these services on my property.

Total	\$0.00
--------------	---------------

Signature: _____

Phone #	Fax #	E-mail	Web Site
(678) 201-5409	(770) 886-1682	phil@SarrosLandscaping.com	www.SarrosLandscaping.com